BANGALORE DIVISION.

Dated 31st December 1929.

Notice is hereby given that sealed tenders will be received at the office of the Ex Engineer, Bangalore Division up to 2 P.M. of 18th January 1930 for Restoring kunte tank Registered 252 of Nelamangala Taluk. An approximate estimate of quan given below. These quantities are not guaranteed. The work should be completed end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive En Office at Bangalore between the hours of 11 A.M. to 5 P.M. (on all working days).

3. Tenders should be submitted on printed forms which may be obtained fr Executive Engineer. The tenders should be accompanied by a statement in the form below, showing the rates at which the different items specified will be executed.

3A. Tenders quoting percentages below or above estimate will not be received.

4. Each tender must be accompanied by a deposit of Rupees 400 in cash or G ment Promissory Notes, as earnest money, and be superscribed "Tender for Re Maralkunte tank Registered 252 of Nelamangala Taluk in default of which, tenders rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, wh not bind himself to accept the lowest or any tender or to assign any reason whatever rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor required to execute the usual contract bond in default of which his tender will be con cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, posted on the notice board in the Executive Engineer's Office in due course. No co regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders returned.

Restoring Maralkunte Tank.

Sl. No.	Items of work	Per	Quantity	R
	Bund R. L. 57·00.			Rs.
1	Cutting grips and jungle clearing	Grade	18	
2	Removing the roots of Pupel tree	L. S.	Rupees	
3	Earthwork to bund including watering and tamping.	C.yd.	10,554	
4	Earthwork for the bracb	,,	4,816	
5	New stone revetment	,,	1,160	
6	Gravel backing	,,	858	
7	Puddle wall (gravel mixed with clay 1:2) ..	...	544	
8	Burnt brick in surki mortar	C.ft.	996	
9	Benching rocky soil ...	S.ft.	276	
10	Plastering with surki mortar	Sqr.	12·42	
11	Old stone work	L. S.	...	
12	Turfing	Sqr.	5,411	
13	Providing new grade stone including cutting figures and painting.	Each	16	
14	Providing index stones	Each	15	
15	Register No. stone	,,	1	
16	B. M. stones	,,	2	
17	Gauge stone	,,	1	
	Constructing a sluice of No. 2 type design.			
1	Dismantling the old sluice	L. S.	Rupees	
2	Earthwork cutting the bund and refilling ..	C.yd.	100	
3	Earthwork excavating foundation... ...	,,	7	
4	Surki mortar concrete	C.ft.	228	
5	Barna stone slabs 6" thick roughly dressed and	S.ft.		

Dated 31st December 1929.

s hereby given that sealed tenders will be received at the Office of the Executive ngalore Division, up to 2 P.M. of 18th January 1930, for construction of uarters at Closepet. An approximate estimate of quantities is given below. ities are not guaranteed. The work should be completed by the end of May 1930. plans, detailed estimate and conditions may be seen at the Executive Engineer's galore, between the hours of 11 A.M. to 5 P.M.

ders should be submitted on printed forms which may be obtained from Engineer. The tenders should be accompanied by a statement in the form showing the rates at which the different items specified will be executed.

lers quoting percentages below or above estimates will not be expected.

tender must be accompanied by a deposit of Rs. 300 (three hundred only) in rament Promissory Notes, as earnest money, and be superscribed "Tender for f Amildar's Quarters at Closepet" in default of which, tenders will be rejected.

final acceptance of any tender will rest with the Executive Engineer, who does elf to accept the lowest or any tender or to assign any reason whatever for f any tender.

in eight days of the acceptance of the tender, the successful competitor will to execute the usual contract bond in default of which, his tender will be nselled, and his earnest money will be forfeited.

name of the successful competitor whose tender has been accepted will be Notice Board in the Executive Engineer's Office in due course. No enquiries acceptance or rejection of a tender will receive any reply.

cceptance of one of the tenders the earnest money on rejected tenders will be

Construction of Amildar's Quarters at Closepet.

Items of work	Per	Quantity	Rate
rk excavation and filling basement	C.yd.	192	Rs.
oundations with burnt stone jelly concrete in mortar	C.ft.	1,304	
one in clay foundation	"	3,989	
ick in clay superstructure	"	3,972	
s pillars 10', 8" sqr.	Each	4	
o 7' x 8' sqr.	"	4	
one slabs 6" thick roughly dressed	S.ft.	586	
ick in chunam as per deducted teakwood panelled s 1½" thick plank.	C.ft.	720	
4" x 5" thick frame and iron fittings, etc. ...	S.ft.	341	
o do front door	"	32	
d windows with ½" diameter 4' x 5' iron bars and panel- tters frame 4" x 5" thick frame and 1" thick plank, etc.	"	188	
d ventilators glazed with ½" iron bars and panelled ters.	"	28	
d battened doors, small	"	15	
d wrought and put up with wood oiling, etc. ...	"	153	
g with mortar	Sqr.	81·58	
shing two coats	"	81·55	
to basement with cement	"	5·46	
with Mangalore tiles 9" x 9" on 3' concrete bed cement pointing.	"	9·52	
with 1½" Kadappa slabs on 3" concrete bed cement ting.	"	5·90	
o painting two coats	"	10·81	
ick in clay parapet wall 2½' high plain with mortar lering complete.	R.ft.	195	

HASSAN DIVISION.

Dated 26th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Engineer, Hassan Division, up to 2 P.M. 16th January 1930, for restoring Kud... Hassan Taluk. An approximate estimate of quantities is given below. These qu... not guaranteed. The work should be completed in two seasons.

2. The plans, detailed estimate and conditions may be seen at the Executive ... Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained ... Executive Engineer. The tender should be accompanied by a statement in the fo... below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred ... or Government Promissory Notes, as earnest money, and be superscribed "Tender i... ing Kudurgundi Tank, Hassan Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engin... does not bind himself to accept the lowest or any tender or to assign any reason wh... the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor ... required to execute the usual contract bond in default of which his tender will be co... cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, ... posted on the notice board in the Executive Engineer's Office in due course. No en... regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders ... returned.

Abstract estimate for restoring Kudurgundi Doddakere Register No. 505, Hassan T... Hassan District.

Sl. No.	Items of work	Per	Quant...
	Bund R. L. 56·00.		
1	Earthwork watering and tamping, lead, etc., complete ...	C.yd.	9,4...
2	Turfing the slopes of bund ...	S.yd	7,7...
3	Grade stones	No.	
4	Index stones	"	
5	Date and Register No. stone	"	
6	B. M. stone	"	
7	Jungle clearing	Grades	
8	New stone revetment	C.yds.	1,1...
9	Removing and resetting with carving and painting grade stones.	No.	
10	Resetting old stone revetment here and there ...	Lump sum	
	Sluice No. 1. R. L. 40·00 (Left side).		
1	Earthwork excavating with lift	C.yds.	2
2	Surki concrete filling foundation	C.ft.	1
3	Burnt brick in surki mortar	"	7
4	Surki plastering	Sqr.	6'
5	Burnt stone slabs 4" to 6" thick dressed and fixed ...	S.ft.	1
6	Boring holes to burnt stone slabs	No.	
7	Cast iron pipe 9" dia. including fixing, 12' length ...	R.ft.	
8	Plug with iron rod and locking arrangement ...	No.	
9	Rough stone work with 3 miles lead	C.yd.	
10	Refilling the excavated earth with consolidation, complete ...	"	2
11	Sundry and unforeseen expenses ...	Lump	

Sl. No.	Items of work 24	Per	Quantity
	Waste Weir Left (50·00)		
1	Clearing draft and approach clearance	Lump	sum
2	Earthwork excavating foundation	C.yds.	26
3	Concrete in surki mortar	C.ft.	285
4	Burnt brick in surki mortar	,,	994
5	Plastering with surki mortar	Sqr.	6·72
6	Cement concrete coping 6" thick over body wall ...	C.ft.	60
7	Rough stone apron	C.yd.	55
	Waste Weir Right (50·00).		
1	Clearing draft and approaches	Lump	sum
2	Earth work excavating foundation	C.yd.	107
3	Concrete in surki mortar	C.ft.	384
4	Burnt brick in surki mortar	,,	1,718
5	Plastering with surki mortar	Sqr.	14·18
6	Cement concrete coping over body wall 6" thick ..	C.ft.	98
7	Rough stone work new, apron	C.yd.	118
8	Putting a jack bund to prevent water flowing over the fields at the left side of right weir.	Lump	sum
9	Providing pin slabs at the end of apron	Lump	sum
10	Providing silt dam	Lump	sum

N. KRISHNA IYENGAR,
Executive Engineer.